



Arbor Cultural Ltd. *Providing Expertise on Your Trees*®

BS5837 Arboricultural Report,

Arboricultural Impact Assessment

and Method Statement

| | |
|---------------------------|---|
| OUR REFERENCE | AC.2021.526 |
| CLIENT | Mr Graham Cox |
| SITE | Land south of Chigwell Cemetery, Chigwell, Essex, IG7 5PS |
| REPORT BY | I S Thompson (known as Tom) M. Arbor. A., BSc. (Hons) Arb, MSc. eFor |
| DATE | 20th November 2021 |
| DATE OF SITE VISIT | 1st November 2021 |

Arbor Cultural Ltd.

West Molesey, Surrey, KT8 2QZ

Phone: 0333 577 5523

W: www.arbor-cultural.co.uk

E: admin@arbor-cultural.co.uk

Land south of Chigwell Cemetery, Chigwell, Essex, IG7 5PS

Application Ref No Unknown

The proposed works consist of five apartment blocks to the centre of the site with associated parking, access roads, infrastructure, and landscaping around the outside. The proposed works also consist of an extension to the existing cemetery area, as part of the proposed development

Report produced by

**I S Thompson MArborA., BSc. (Hons) Arb MSc. eFor
Principal Arboricultural Consultant**

**Arbor Cultural Ltd.
36 Central Avenue,
West Molesey, Surrey, KT8 2QZ
Phone: 0333 577 5523**

W: www.arbor-cultural.co.uk

E: admin@arbor-cultural.co.uk

Signed



.....

Date.....11th November 2021.....

Table of Contents

| | |
|---|----|
| Executive Summary | 1 |
| 1 Terms of Reference | 4 |
| 1.5 Limitations and Use of Copyright: | 5 |
| 1.7 Documentation | 6 |
| 1.8 Disclaimer | 7 |
| 2. Introduction | 8 |
| 2.1 Site..... | 8 |
| 2.2 Trees | 8 |
| 2.3 Proposed Development | 10 |
| 2.4 Issues of Light and Shading | 10 |
| 2.5 Description (including levels) | 11 |
| 2.6 Soils | 11 |
| 3 Arboricultural Impact Assessment | 12 |
| 3.1 Presence of Tree Preservation Orders (TPO) or Conservation Area Designation | 12 |
| 3.2 Effects on the amenity value of the trees by the development and facilitation pruning. | 12 |
| 3.3 Potential incompatibilities between the layout and the trees proposed for retention..... | 13 |
| 3.4 Infrastructure requirements – Highway Visibility, Lighting, CCTV, Services | 14 |
| 3.5 Mitigating tree loss and new planting | 14 |
| 3.6 Proximity of trees to structures | 14 |
| 3.7 Issues to be addressed by the arboricultural method statement. | 15 |
| Arboricultural Method Statement | 16 |
| 1 Construction Exclusion Zone | 16 |
| 2 Ground Protection Measures | 18 |
| 3 Access Details..... | 18 |
| 4 Contractors car parking | 18 |
| 5 Site Huts and Toilets..... | 18 |
| 6 Storage Space..... | 18 |
| 7 Additional Precautions | 19 |
| 8 Demolition | 20 |
| 9 Hard Surfaces within the RPA..... | 20 |
| 10 Construction within the RPA (No-dig)..... | 20 |
| 11 Foundation Designs..... | 21 |
| 12 Remedial Tree Works | 21 |
| 13 Use of Herbicides | 22 |
| 14 Contingency Plan..... | 22 |
| 15 Responsibilities | 23 |
| 16 Arboricultural Supervision..... | 24 |
| 17 Landscaping and Replacement Planting | 28 |
| References and Bibliography and Glossary of Terms..... | 29 |
| Appendix I Abridged CV; Qualifications and Experience | 32 |
| Appendix II Specifications for Tree Protection Measures..... | 34 |
| Appendix III Key to BS5837 Tree Survey Records | 38 |
| Appendix V Arboricultural Supervision Recording Template..... | 50 |
| Appendix VI Tree Survey Records | 51 |

Executive Summary

The proposal is to construct five apartment blocks to the centre of the site with associated parking, access roads, infrastructure, and landscaping around the outside on land south of Chigwell Cemetery, Chigwell, Essex, IG7 5PS.

The proposed works also consist of an extension to the existing cemetery area, as part of the proposed development.

The impact of the retained trees on the proposed building and vice a versa have been assessed and found to be consistent with the long-term health of the retained trees and sustainability of the building provided that build and protection methods in accordance with industry best practice and BS 5837: 2012 (Trees in relation to design, demolition and construction – recommendations), are followed as specified.

This report includes supporting arboricultural information to accompany the planning application. The supporting information demonstrates that there will be no encroachment into the RPAs (Root Protection Areas), of any protected trees as a result of the proposed development. The tree protection measures, and any mitigation measures are also outlined.

The Nation Planning Policy Framework (NPPF) document further emphasizes the importance of trees and the natural environment.

“Planning policies and decisions should contribute to and enhance the natural and local environment by:

- a) protecting and enhancing valued landscapes, sites of biodiversity or geological value and soils (in a manner commensurate with their statutory status or identified quality in the development plan);
- b) recognising the intrinsic character and beauty of the countryside, and the wider benefits from natural capital and ecosystem services – including the economic and other benefits of the best and most versatile agricultural land, and of trees and woodland,” (NPPF, July 2021).

Possible conflicts are;

There are 18 trees that require their Root Protection areas (RPAs) to be protected during the proposed development.

This is addressed Arboricultural Method Statement (AMS) Section 1, Construction Exclusion Zone, as shown on the tree protection plan AC.2021.526 TPP-01 Rev A.

Site access is addressed in Section 3 of the AMS, Access Details, and on the tree protection plan AC.2021.526 TPP-01 Rev A.

The AMS addresses Contractors' Car Parking in Section 4, Site Huts and Toilets in Section 5, and Storage Space in Section 6, and on the tree protection plan AC.2021.526 TPP-01 Rev A.

There are some recommendations for tree work. This is in Section 12 of the AMS, Remedial Tree Work.

The recommendations for supervision are addressed in Section 16 of the AMS, Arboricultural Supervision.

1 Terms of Reference

1.1 I have been instructed in writing by Mr Graham Cox of Kind Build with regards to a planning application to be made by himself in respect of the above development on land south of Chigwell Cemetery, Chigwell, Essex, IG7 5PS and report on the following in accordance with BS 5837 Trees in Relation to Design, Demolition and Construction - Recommendations 2012:

- I. Tree survey
- II. Arboricultural Impact Assessment
- III. Arboricultural Method Statement
- IV. Tree Protection Plan

1.2 The site was surveyed by I. S. Thompson (known as Tom) on Monday 1st November 2021 in the afternoon. The weather was dry and sunny, and visibility was good. The relative quantitative and qualitative tree data was recorded to assess the condition of the trees, their value, and any constraints that they pose to the prospective development and where necessary the tree protection measures, and construction methods required to ensure their safe retention.

1.3 The tree information recorded relates to the tree condition, age, safe useful life expectancy, location, canopy spread, canopy height and tree height and direction of first significant branch as well as any tree work that is required.

1.4 I have based this report on my site observations and investigations, and I have come to conclusions in the light of my qualifications obtained and experience gained whilst working in the field of arboriculture. I have qualifications and practical experience in arboriculture and forestry and list the details in Appendix I.

1.5 Limitations and Use of Copyright:

- 1.5.1** All rights in this report are reserved. No part of it may be reproduced or transmitted, in any form or by any means without our written permission. Its contents and format are for the exclusive use of Mr Cox and his associates. It may not be sold, lent out or divulged to any third party not directly involved in this situation without the written consent of Arbor Cultural Ltd. This report will remain the intellectual property of Arbor Cultural Ltd. until payment has been received in full.
- 1.5.2** This report contains all my advice and opinions and any representation and/or statements that have or may have been made which are not specifically and expressly included in this report should not be relied upon and no responsibility is taken for the accuracy of such statements.
- 1.5.3** The Inspections were carried out based on ground level, Visual Tree Assessment (VTA) examination of external features of each individual tree. Binoculars were used to assess the aerial parts. The report and recommendations relate to the condition of the trees and their relationship to their surroundings at the time of inspection only. All measurements, proportions and assessments of age are approximate.
- 1.5.4** Visual assessment, in accordance with accepted arboricultural practice, was based on apparent vitality (leaf cover, extension growth), presence of deadwood and die back, fractured, and detached limbs, evidence of excessive basal movement and external indications of stem and basal decay likely to affect the structural condition of the tree. No decay detection equipment either invasive or non-invasive was employed.

1.5.5 Trees are living organisms whose health and condition can change rapidly. The conclusions and recommendations in this report are only valid for one year. This report will be invalidated if there are any changes to the site as it stands at present, e.g., building of extensions, excavation works, importing of soils, extreme weather events etc.

1.5.6 The survey findings are of a preliminary nature regarding assessment of risk of direct damage (by contact) from trees to built structures. No soil samples were taken, or trial pits were dug, therefore no risk assessment was carried out regarding subsidence (indirect damage). No parts of the drainage or service systems were inspected on site as I am not qualified to do so.

1.6 A principal aspect of tree inspections in relation to proposed developments is an assessment of the risk posed by trees in proximity to people or property. Generally, tree risk will increase with the age of the trees. The benefits afforded by the trees will also increase with age. The management recommendations will be guided by an analysis of the risk posed by the trees and the benefits afforded by them.

1.7 Documentation

1.7.1 The following documentation was provided when the work was commissioned.

- Letter/Email to confirm commission of the work.
- Plan of the site, Ref LL488-200-0001P1, received on 17th November 2021 showing the existing and proposed layout.

1.8 Disclaimer

1.8.1 I have no connection with any of the parties involved in this situation that could influence the opinions expressed in this report.

1.8.2 Following an initial site visit to assess the likely position of the proposed development, the following arboricultural information is provided in support of the application.

2. Introduction

2.1 Site

2.1.1 The site of the proposed development is within the current boundary of land south of Chigwell Cemetery, Chigwell, Essex, IG7 5PS, and will be adjacent to several currently unprotected but significant trees. Following the site meeting the measures identified in this report are designed to minimise any likely impacts of the trees on the new structure and its foundations and any likely impacts of the construction on the retained trees, see plan AC.2021.526 TPP-01 Rev A attached.

2.2 Trees

2.2.1 Some of the trees are in the cemetery with many along the site boundary with the proposed development site on land to the west of Froghall Lane, Chigwell, see Images 1 to 9. The groups of trees G1 to G5 are on the current site along with two hedge, H1 and H2, see Images 10 to 15. They collectively provide a contribution to the appearance and character of the cemetery, Froghall and the surrounding area. A schedule of the significant trees, their condition and category of retention is attached as Appendix VI.

2.2.2 An accurate topographical survey of the site was not provided. The tree locations were measured in relation to the site boundaries and other known features and triangulated and are accurate to +/-1.5m. So, the drawing number AC.2021.526 TPP-01 Rev A provides a good representation of the tree location in relation to the site and the proposed development.

- 2.2.3** The trees have been assessed and categorised in relation to the methodology in Table 1 of BS 5837 (2012) Trees in Relation to Design, Demolition and Construction, as specified in Appendix III. The results are recorded in Appendix VII.
- 2.2.4** There were a total of 80 individual trees surveyed. This comprised of 8 ash trees, one goat willow, four white willow, a silver birch, a robinia, 10 hawthorn, 43, Leyland cypress trees, and 12 oak trees. There were no A category trees, 52 B1 category trees, 15 B2 category trees, eight C1, category, and four C2 category trees with one U category tree.
- 2.2.5** There were also five groups of self-set scrub comprising of mostly hawthorn and bramble, which were all classified as C2. There were also cypress hedges, classified as C2's.
- 2.2.6** Any trees not included individually in the survey were either in groups or had other trees whose constraints exceeded theirs in respect to the proposed development and all associated works.
- 2.2.7** All tree works considered necessary for health and safety reasons or to facilitate the development will be agreed with the Local Planning Authority and undertaken in accordance with the planning conditions attached to the planning consent. They will be undertaken in accordance with British Standard 3998 (2010) Recommendations for Tree Works, unless otherwise specified with clear justification for any deviation from the British Standard. This will be undertaken by an arboricultural contractor approved by the Local Authority Tree Officer.

2.2.8 If at any time additional pruning works are required permission must be sought from the Local Planning Authority first and then carried out in accordance with BS 3998 Recommendations for Tree Works (2010), unless otherwise specified with clear justification for any deviation from the British Standard. This will be undertaken by an arboricultural contractor approved by the Local Authority Tree Officer.

2.3 Proposed Development

2.3.1 The proposed works consist of five apartment blocks to the centre of the site with associated parking, access roads, infrastructure, and landscaping around the outside.

2.3.2 The proposed works also consist of an extension to the existing cemetery area, as part of the proposed development.

2.4 Issues of Light and Shading

2.4.1 The proposed position of the new dwellings will not be shaded by any retained trees. This will allow adequate sunlight to reach all the windows during the summer and winter months.

2.4.2 It is not anticipated that the proposed development will increase pressure for tree pruning or tree removal due to shading or the loss of natural light.

2.5 Description (including levels)

2.5.1 This is currently an area of pastoral farmland with some emerging scrub woodland, mostly comprising of hawthorn, birch, and gorse, with a row of Leyland cypress trees along the existing northern boundary line. The site slopes slightly downwards from north to south.

2.6 Soils

2.6.1 There is no information provided about the soils and there was no investigation undertaken. From the British geological Service (BGS) website it is likely that the soil is London Clay mainly comprised of bioturbated or poorly laminated, blue-grey, or grey brown, slightly calcareous, silty to very silty clay, clayey silt and sometimes silt, with some layers of sandy clay, (BGS Viewer, 2021).

2.6.2 The BGS viewer has no information about the likely drift layer, (BGS Viewer, 2021).

2.6.3 It is likely that the soil below foundation depth will be of a shrinkable nature.

3 Arboricultural Impact Assessment

3.1 Presence of Tree Preservation Orders (TPO) or Conservation Area Designation

3.1.1 The Local Planning Authority has not yet been contacted to establish whether any Tree Preservation Order (TPO) covers any of the trees, or to determine if the site is situated within a Conservation Area (CA). It would be necessary to determine whether either of these planning controls are in operation before commencement of any tree works.

3.1.2 The client has informed me that there are no TPOs in place and it is not in a Conservation Area. I have not verified with the LPA.

3.1.2 Exemptions

There are two exemptions when this notification or permission are not required. They are detailed below:

- Removal of an imminent threat to people or property
- Removal of deadwood or dead trees

3.2 Effects on the amenity value of the trees by the development and facilitation pruning.

3.2.1 There are two oak trees T12 and T13 that are to be removed for the access road a B1 and C1 category tree respectively, and an ash tree T22 a B1 category tree is to be removed for one of the apartment blocks. There is also a U category oak tree that is to be removed due to its poor condition.

3.2.2 For the additional grave space there are only two individual trees that are proposed for removal. These are T45 and T46 both semi mature Leyland cypress trees to make way for the new access. Additionally, most of G1, comprising of scrub woodland predominantly hawthorn and gorse with some ash saplings all less than 75mm in diameter will be removed to make way for new grave spaces. Consequently, there will be a minimal effect to their amenity value of the area.

3.3 Potential incompatibilities between the layout and the trees proposed for retention.

3.3.1 There is no proposed construction of foundations within the RPA of any retained trees.

3.3.2 There will not be any services installed within any Root Protection Area (RPA). The services will be run into the site along the new access that is to be created.

3.3.3 The crowns of all retained trees will remain unaffected by the proposed development. All tree surgery works will be undertaken prior to construction activity and in accordance with the Arboricultural Method Statement Section 12 Remedial Tree Works.

3.3.4 Site access will be from the south-western end of the site via Woodland Road, or from the western edge of the site via Mount Pleasant Road. These are the two new entrances that are being created for the site.

3.4 Infrastructure requirements – Highway Visibility, Lighting, CCTV, Services

3.4.1 There is no requirement for any tree removal or pruning to create adequate highway visibility. There will be no requirement for street lighting or CCTV visibility, or services close to any of the trees.

3.4.2 No services or other infrastructure requirements will have any impact on the retained trees.

3.5 Mitigating tree loss and new planting

3.5.1 The landscaping is being addressed in a separate plan and methodology.

3.6 Proximity of trees to structures

3.6.1 The impact of trees on buildings and vice versa and allowance for future growth have all been considered in the siting of the new buildings and structures. Tree size, future growth, light/shading, leaf, and fruit nuisance etc. have received due attention and are not considered to be an issue. This is due to the considerable distance of the retained trees from the development and the protection measures proposed within this report.

3.6.2 The structure has been placed well outside of the RPAs of trees and therefore exceeds the recommendations of BS 5837.

3.6.3 Overall, the processes of construction are highly unlikely to have a detrimental effect upon the health of the retained trees assuming recommendations made in this report are adhered to at all times by the contractors e.g., the positioning of a stout fence is placed between the retained trees and all construction activities prior to commencement of any works and for it to remain intact and in position throughout the duration of the construction activities.

3.7 Issues to be addressed by the arboricultural method statement.

- **Protective fencing to be established around the retained trees.**
- **Site access**
- **Contractor's parking, welfare facilities and storage areas**
- **Remedial tree work**

Arboricultural Method Statement

Tree Protection throughout the Duration of Demolition and Construction Works

All the details specified in this method statement will need to be supervised by an Arboricultural Consultant with suitable qualifications and experience.

Arboricultural Method Statement includes a Tree Protection Plan to identify:

- Trees to be retained – identified with a dashed line with RPA written within it and green, blue, or grey location marker circles and the corresponding A, B or C category label.
- Protective fence positions identifying the Construction Exclusion Zones (CEZ).
- Measurements to identify fence positioning in relation to centre of tree or other known features.
- Contractor huts and storage areas

1 Construction Exclusion Zone

1.1 No works will be undertaken within any Construction Exclusion Zone (CEZ). The CEZs are to be afforded protection at all times and will be protected by fencing. A protective fence shall be erected prior to the commencement of any site works e.g., before any materials or machinery are brought on site, development or the stripping of soil commences.

1.2 The fence shall have signs attached to it stating that this is a Construction Exclusion Zone and that **NO WORKS are Permitted within the fence**, see Image 4 in Appendix II. The tree protection fencing may only be removed following completion of all construction works.

- 1.3 The fence is required to be sited in accordance with the Tree Protection Plan Reference AC.2021.526 TPP-01 Rev A enclosed with this method statement.
- 1.4 They must be constructed as per Figures 1 and 2 in BS 5837 2012 and be fit for excluding any construction activity, (See Appendix II). Any other fence or barrier used must be fit for the purpose.
- 1.5 The fencing unless otherwise agreed with the tree officer shall consist of Heras fencing panels, around 3.5m long and 2 m tall. They shall be fixed into the ground on scaffold poles driven at least 1 m into the ground. They shall be supported by rear struts also secured to posts driven into the ground, see Figure 1 in Appendix II.
- 1.6 All bolts shall be secured from inside the fencing to prevent easy removal from the outside during the construction phase.
- 1.7 Where there are **existing hard surfaces**, then rubber feet can be used to support the fencing, but these rubber feet shall be secured into the ground with road pins or other robust metal pins, to prevent the fencing being moved. This stall also be secured by rear struts which are also pinned into the ground, see Figure 2 in Appendix II.
- 1.8 All tree protection fencing shall be regarded as sacrosanct and will not be removed or altered without prior written consent of the Local Authority Tree Officer.

2 Ground Protection Measures

- 2.1** The tree protection fencing will extend to the full extent of the RPA of all retained trees, so there is not requirement for any ground protection measures as part of this development.

3 Access Details

- 3.1** All access for construction vehicles will be from the south-western end of the site via Woodland Road, or from the western edge of the site via Mount Pleasant Road. These are the two new entrances that are being created for the site, as shown on the plan AC.2021.526 TPP-01 Rev A.

4 Contractors car parking

- 4.1** This will be on-site as shown on the tree protection plan AC.2021.526 TPP-01 Rev A.

5 Site Huts and Toilets

- 5.1** This will be on-site, as shown on the tree protection plan AC.2021.526 TPP-01 Rev A.

6 Storage Space

- 6.1** This will be on-site, as shown on the tree protection plan AC.2021.526 TPP-01 Rev A.

7 Additional Precautions

- 7.1** No storage of materials or lighting of fires will take place within any construction Exclusion Zone. No mixing or storage of materials will take place up a slope where they may leak into a Construction Exclusion Zone.
- 7.2** There shall generally be a presumption against burning on site. Where it does occur, no fires will be lit within 20 metres of any tree stem and will consider fire size and wind direction so that, no flames come within 5m of any foliage. Situations where fires are not permitted at all are:
- Where the ground is waterlogged as the heat will transfer through the water and damage tree roots significant distances away.
 - During periods of drought, where there are peaty or highly organic soils, as there is a risk of underground fires occurring.
- 7.3** No notice boards, cables or other services will be attached to any tree.
- 7.4** Materials which may contaminate the soil will not be discharged within 10m of any tree stem. When undertaking the mixing of any material it is essential that, any slope of the ground does not allow contaminants to run towards a tree root area.
- 7.5** No materials that are likely to have an adverse effect on tree health such as oil, bitumen or cement will be stored or discharged within 10 meters of the trunk of any retained trees. In the event of any accident of spillage in or adjacent to the protected trees the contractor/staff is to immediately stop work in the vicinity and inform the project arboriculturist.

- 7.6** In the event of spillage, the area is to be secured with sandbags on the line of the tree protection area and measures taken to drain/soak any spillage away from the protected area.

8 Demolition

- 8.1** There will be no demolition within any of the RPAs of retained trees, so there will not need to be any special measures or precautions undertaken other than the tree protection measures as detailed in the report and in AC.2021.526 TPP-01 Rev A, which shall be installed prior to any site works commencing.

9 Hard Surfaces within the RPA

- 9.1** There is no construction of any new hard surfaces within the RPA of any retained trees, so there is no requirement for any no-dig surface construction method statements.

10 Construction within the RPA (No-dig)

- 10.1** There is no construction within the RPA of any retained trees, so there is no requirement for any construction method statements to address this issue.

11 Foundation Designs

- 11.1** As there is no construction of foundations within the RPA of any retained trees there will be no requirement for any alternative foundation designs.

12 Remedial Tree Works

- 12.1** Tree works (see schedule at Appendix VII) will be undertaken in one phase, and this will be undertaken prior to any construction or demolition works and prior to the installation of any tree protection measures. All tree works are to be carried out in accordance with BS 3998 (British Standard Recommendations for Tree Work 2010) unless otherwise specified with clear justification for any deviation from the British Standard.
- 12.2** There are six trees that are proposed for removal as part of this applications. These are two oak trees T12 and T13 that are to be removed for the access road, and an ash tree T22 to be removed for one of the apartment blocks. There is also a U category oak tree that is to be removed due to its poor condition. G05 some self-set saplings and scrub will be removed.
- 12.3** For the additional grave space there are only two individual trees that are proposed for removal as part of this application. These are T45 and T46 both semi mature Leyland cypress trees to make way for the new access. Additionally, most of G1, comprising of scrub woodland predominantly hawthorn and gorse with some ash saplings will be removed to make way for new grave spaces.

12.4 If at any time additional pruning works are required permission must be sought from the Local Planning Authority first and then carried out in accordance with BS 3998 Recommendations for Tree Works 2010, unless otherwise specified with clear justification for any deviation from the British Standard.

12.5 Ideally tree surgery work and shrub and hedge removal should take place outside of the bird nesting season which is officially from February to August. As this is small-scale works with a relatively low cost this should be undertaken as soon as any planning permission is obtained so that it is completed before February and does not hold up any site works.

12.6 Tree work can be done in the bird nesting season but would require a watching brief of 20 minutes to check for bird activity and cannot proceed if bird nests are found to be present.

13 Use of Herbicides

13.1 It is not planned to use any herbicide in the proposed development unless they are used in the preparation of any no-dig construction. However, if any is required it shall be systemic, spot applied, and mixed according to manufacturer's recommendations.

14 Contingency Plan

14.1 Water is readily available on site and will be used to flush spilt materials through the soil and avoid contamination to tree roots. At the time of any spillage the main contractor will contact an arboriculturist for advice.

15 Responsibilities

- 15.1** It will be the responsibility of the main contractor to ensure that the planning conditions attached to planning consent are adhered to always and that a monitoring regime regarding tree protection is adopted on site.
- 15.2** The main contractor will be responsible for contacting the Local Planning Authority at any time issues are raised related to the trees on site.
- 15.3** The main contractor will ensure the build sequence is appropriate to ensure that no damage occurs to the trees during the construction processes. Protective fences will remain in position until completion of **ALL** construction works on the site.
- 15.4** The fencing, signage and ground protection measures must be maintained in position at all times and shall be checked on a regular basis by an on-site person designated that responsibility.
- 15.5** The main contractor will be responsible for ensuring sub-contractors do not carry out any process or operation that is likely to adversely impact upon any tree on site or those immediately adjacent to it.

16 Arboricultural Supervision

16.1 Since BS5837 was amended in 2012 site supervision has been identified as a key element of the process of protecting trees during construction. It requires that there be “an auditable system of arboricultural site monitoring. This should extend to arboricultural supervision whenever construction and development activity is to take place within or adjacent to any RPA.”

16.2 Site Supervision

16.2.1 A site agent must be nominated to be responsible for all arboricultural matters on site. They must be nominated for each phase of work if demolition and construction contracts are to be awarded separately. The agent(s) must:

- **Be present on site for most of the time.**
- **Be aware of the arboricultural responsibilities. This will require a site briefing/meeting between the agent and arboricultural consultant prior to the commencement of each phase of works.**
- **Have the authority to stop any work that is causing or has the potential to cause harm to any trees.**
- **Be responsible for ensuring that all site operatives are aware of their responsibilities towards trees on the site and the consequences of failure to observe these responsibilities.**
- **Make immediate contact with the local authority and/or a retained arboriculturist in the event of any tree related problems occurring, whether actual or potential**
- **Contact details for Arbor Cultural Ltd are provided within this report.**
- **Contact details for local authority tree officer are;**

Tree officer **Mr Robin Hellier**
Address. **Epping Forest District Council Civic Offices, 323 High Street, Epping,**
 CM16 4BZ
Main Switchboard **01992 564000**
Email trees@eppingforestdc.gov.uk

16.3 Arboricultural Consultant

16.3.1 A suitably qualified arboricultural consultant shall be appointed to oversee development works and liaise with the council and the developer and contractors during the construction phase to ensure compliance with these guidelines.

16.3.2 Note: Failure to fulfil planning conditions or breaches of statutory legislation can lead to delays due to “stop notices” and can lead to the prosecution of contractors and company directors.

16.3.3 Adequate site supervision can protect the developer from delays, stop notices, wasted expense and criminal prosecution.

16.3.4 The arboriculturalist will arrive at the site, check in at the site office and be safely escorted around the site by the site agent, checking the maintenance of tree protection measures. Routine visits will generally be unannounced. However, the arboriculturist will also visit subject to advance notification and agreement to supervise any agreed works within the RPA.

16.3.5 Monitoring shall involve a schedule of routine visits. The frequency of these visits will vary depending on the size of the proposed development and the site-specific constraints. For private single residential developments, this will normally involve monthly supervision but for larger sites with multiple structures this could be weekly or fortnightly. This will need to be agreed with the local tree officer.

16.3.6 These visits shall include a pre-commencement meeting to ensure that all tree protection measures have been implemented and a sign-off sheet at the end of the development. Each visit will be accompanied by a small report detailing the findings identifying any actions and addressing any issues that have arisen. This is to provide ongoing liaison between the local planning authority (LPA), and all personnel involved in the site development. Any defects requiring rectifying must be notified to the site agent the client and the LPA by email as soon as possible.

16.3.7 Emergency situations will be notified by phone calls. Appropriate records will be kept and made available to the LPA if required to show evidence of the site monitoring. An example of this is shown in Appendix V.

16.3.8 Supervision will not require the arboriculturist to be present throughout all operations, to ensure that all tasks are carried out as per the approved methodology. They will be required at key times during any planned or unplanned incursions into the tree protection areas. This supervision will require the arboriculturist to attend site, if not for the whole task, then long enough to ensure that all the arboricultural objectives are fully addressed. Where tasks are ongoing, provided that the arboriculturalist is satisfied that the method statement is being followed and after an appropriate briefing the supervision may be reduced to telephone or email contact between the site supervisor and the arboriculturist.

16.4 The critical stages for site supervision are as follows:

- I** Prior to the start of construction, all tree protection measures as described must be checked as appropriate and signed off by an arboriculturalist. There will be a pre-commencement meeting with all party attendance, including LPA tree officer, to ensure that there are no unresolved issues.
- II** At predetermined activity related times as specified in Table 1. The tree protection measures as described must be checked as being retained and signed off by an arboriculturalist. All defects to be reported to the client and LPA.
- III** The potentially damaging activity to the trees must be observed by a suitably qualified arboriculturalist to ensure that the method statements are adhered to, and the damage is kept to an absolute minimum. All defects to be reported to the client and LPA.
- IV** At periodic intervals during the construction process, the tree protection measures must be checked as being retained and signed off. All defects to be reported to the client and LPA.
- V** At the end of the construction phase, an arboricultural consultant must check that no damage has occurred to the trees and any remedial measures, e.g., de-compaction of soil must be recommended as required and remedial measures undertaken as soon as practicable. The outcome shall be reported to the client and local authority.

16.4.1 The site supervision visits will be documented and circulated to the site agent, developer, architect, and Local Planning Authority as appropriate. The reports will detail the date of the visit, the operations being supervised and any issues that require action to meet the aims and objectives of this method statement.

Table 1 Site Supervision Programme

| | Activity | Comments |
|--------------|---|--|
| 1 | Inspection of all tree protection measures to ensure that it is secure and fit for purpose prior to work commencing. This will need to be signed off by the arboriculturalist. | Report any defects or damage to the client and the LPA and ensure that they are made good. |
| 2 | Pre-commencement meeting with all party attendance, including LPA tree officer, to ensure that there are no unresolved issues. This will need to be signed off by the arboriculturalist. | Report any defects or damage to the client and the LPA and ensure that they are made good. |
| 3 | Monthly monitoring of site and tree protection measures. This will need to be signed off by the arboriculturalist. | Report any defects or damage to the client and the LPA and ensure that they are made good. |
| Final | Completion of work, removal of all tree protection measures and inspection of trees and root zone for any damage. Any compaction of the soil must be rectified with remedial measures and damaged branches taken back to suitable growth points with a clean cut. This will need to be signed off by the arboriculturalist. | Report any defects or damage to the client and the LPA and ensure that they are made good. |

17 Landscaping and Replacement Planting

17.1 The landscaping is being addressed in a separate plan and methodology.

References and Bibliography and Glossary of Terms

References and Bibliography

- Anon, British Standard BS 5837 (2012), "Guide for Trees in Relation to Construction", British Standards Institute. London.
- Anon, British Standard BS 3998 (2010), "Recommendations for Tree Work", British Standards Institute. London.
- Biddle, PG., (1998), "Tree Root damage to Buildings", Willowmead Publishing Ltd. 2 Volumes, 376 & 299 pp.
- Building Research Establishment, BRE Digests 63, 64, 67, Soils & Foundations, 240, 241 & 242, Low Rise Buildings on Shrinkable Clay Soils.
- Cutler, D.F., (1995), "Interactions of Tree Roots & Buildings", In Watson, G., and Neely, D., (Eds.), Proceedings of Trees & Buildings Conference, Lisle, Illinois, ISA Publications.
- Cutler, D. F., and I.B.K. Richardson, (1989). Tree Roots and Buildings. Longman Scientific and technical. 2nd Ed. 71pp.
- DOE, "Tree Preservation Orders – A guide to the law and good practice," Department of Environment, 1994.
- Gasson, P.E. and Cutler, D.F. (1990) Tree root plate morphology. Arboricultural Journal 14, 193-264
- Mercer G., Reeves A., and O'Callaghan D. (2012) The Relationship between Trees, Distance to Buildings and Subsidence Events on Shrinkable Clay Soil, Arboricultural Journal: The International Journal of Urban Forestry, 33:4, 229-245
- National House Building Council, (1992) Building near trees. NHBC Standards, Chapter 4.2
- Town & Country Planning Act Part VIII (1990). Issued by the Secretary of State for the Environment, HMSO.

Glossary of Terms

| | |
|-----------------------------|--|
| Bacterial canker | Has lesions on the stems that can exude a gum like exudate that carries the bacteria. |
| Brash | Thin wood removed from trees. |
| Chlorosis/Chlorotic. | An abnormal yellowing or blanching of the leaves due to lack of chlorophyll. |
| Canopy/Crown | Foliage bearing part of the tree. |
| Crown lifting. | The removal of the lower branches of the tree. |
| Crown thinning. | The complete removal of selected limbs/lateral branches to thin the density of the crown. |
| Dysfunctional wood | Woody tissues no longer function. |
| Epicormic growth | Young, vigorous shoots arising from the external tissues of a stem. Epicormic growth is usually induced if a limb is removed or is broken off and the light factor changes (sprouts) or if a woody plant is coppiced or pollarded. |
| Flush cut | A pruning cut close to the parent stem which removes part of the branch bark ridge. |
| Heartwood | The heartwood is the dark area in the centre of the tree. |
| Lateral branch | A side branch which arises from a main stem. |
| Mulch | A layer of bulky organic material placed around the stem. |
| Occlusion (Occluded) | The process of wound wood closing a wound. |
| Parasitic | Organisms that live off other organisms, or hosts, to survive |
| Pathogen | A micro-organism which causes disease in another organism. |
| Reaction Wood | Additional wood that is put on by a tree to address increased loads. |
| Reaction Zone | An area where reaction wood is formed. |

Glossary of Terms Continued

| | |
|---------------------|---|
| Saprotrophic | Organisms that at obtain their nutrition from non-living organic materials. |
| Soft rot | A kind of wood decay in which a fungus degrades cellulose within the cell walls, without causing overall degradation of the wall. |
| Stem | Principal above ground structural component(s) of a tree that supports its branches. |
| White rot | Various kinds of wood decay in which lignin, usually together with cellulose and other wood constituents is degraded. |
| Wound | Injury in a tree caused by a physical force. |
| Wound Wood | Additional wood that it put on by a tree is reaction to damage or wounding, with the aim of healing over the wound. |

Appendix I Abridged CV; Qualifications and Experience

I S Tom Thompson BSc (Hons Arb), MSc eFor, MArborA Cert Arb

1 Qualifications

| Subjects | Level | Dates |
|---|---------------|------------|
| Bond Solon Expert Witness Training (CUBS) | Pass | 2017 |
| International Society of Arboriculture Certified Arborist | Pass | May 2012 |
| Professional Tree Inspection Course (LANTRA) | Pass | April 2011 |
| BSc Hons Arboriculture | (2.1) | 2008 2009 |
| FdSc Arboriculture | Distinction | 2004 2007 |
| MSc. Environmental Forestry (MSc eFor) | Pass | 2001 2002 |
| BSc. Hons Env Science (Conservation Management) | (2.2) | 1997 2000 |
| Environmental Studies | Access Course | 1996 1997 |
| Forestry & Practical Environmental Skills | NVQ I & II | 1996 1997 |

2 Career Summary

Tom Thompson is a professional member of the Arboricultural Association (AA), an International Society of Arboriculture (ISA) Certified Arborist, Chairman of the Consulting Arborist Society (CAS), and an associate member of the Institute of chartered Foresters (ICF).

He has worked in the private and public sector, before setting up Arbor Cultural in 2014, to promote the value and benefits of trees.

He currently heads up the BIM4Arb group promoting Building Information Modelling (BIM) to the arboricultural industry.

He then spent five years working in new woodland creation, firstly for ADAS in the National Forest and then for 18 months with the Forestry Commission in Cobham, Kent. During this time, he began a degree in Arboriculture through Myerscough College.

This course enabled him to make the transition from forestry to arboriculture where he spent 5 years as a tree officer, firstly at St Albans and then more recently at King's Lynn and West Norfolk. He joined Connick Tree Care in May 2012, where he worked as their Principal Arboricultural Consultant.

Having worked as the principal tree consultant at Connick tree care for two years he left to establish Arbor Cultural Ltd. In 2014, with the intent to provide professional advice in all aspects of tree consultancy, to enable clients to obtain planning permission, house purchase completion, and successfully address all tree related health and safety matters. He is passionate about trees, and he is keen to promote the economic value and benefits of the urban forest.

3 Areas of Competence

- Tree hazard risk assessments for tree owners
- Decay assessment and mapping
- Mortgage and Insurance reports to assess the influence of trees on buildings.
- Pre-development site surveys and arboricultural implication studies
- Tree management reports to prioritise maintenance programs.
- Tree related insurance claims
- Diagnosis of tree disorders
- Arboricultural Expert Witness

4 Selected Continual Professional Development

| Training | Provider | Date | |
|-----------------------------------|---------------------------------|------|------|
| Digital Integration Workshop | Landscape Institute | Jan | 2020 |
| Tree Planting conference | Palmstead Nursery | Jan | 2020 |
| Climate Change | Westminster Briefing | Dec | 2019 |
| Subsidence Report Writing | Consulting Arborist Society | Nov | 2019 |
| London Plane Conference | London Tree Officer Association | July | 2019 |
| VALID Tree Inspection Procedures | David Evans | June | 2019 |
| Expert Witness Conference | Bond Solon | Nov | 2018 |
| AA Registered consultant Workshop | Arboricultural Association | Nov | 2018 |
| iTree Seminar | Barcham Nursery | Nov | 2018 |
| Tree Safety and Beyond | MTOA & Frank Rinn | Sept | 2018 |
| Claus Mattheck Workshops | Sorbus | June | 2018 |
| Expert Witness Conference | Bond Solon | Nov | 2017 |
| Decay Workshops | MTOA & Frank Rinn | Sept | 2017 |
| Mortgage Report Writing | Lantra and CAS | June | 2017 |

5. Professional Affiliations

| | |
|---|------------|
| Arboricultural Association (AA) Professional Member | since 2008 |
| International Society of Arboriculture (ISA) Certified Arborist | since 2012 |
| Consulting Arborists Society (CAS) | since 2014 |
| Institute of Chartered Foresters Associate Members | since 2018 |
| Royal Forestry Society | since 1999 |

Appendix II Specifications for Tree Protection Measures




Figure 1 Default Tree Protection Fencing Design for All Soft Ground (BS5837 2012)




Figure 2 **Tree Protection Fencing Design for Hard Surfaced Areas Only (BS5837 2012)**




Figure 3. – Scaffolding within the RPA



CONSTRUCTION EXCLUSION ZONE

**This area has been identified as a Tree Protection Zone.
No Access is to be Permitted**

**Do Not Enter Without Specific Instruction
from the Tree Officer or Project Arboricultural Consultant**

Figure 4 Construction Exclusion Zone Signage

Appendix III Key to BS5837 Tree Survey Records

Tree No. Tree numbers applied as T1 etc. to each tree are as per the Tree Survey Plan and subsequent drawings, where trees occur as a cohesive group these are suffixed with a G, they are assessed as such, with all size data being given as mean figures unless otherwise stated. Any trees on-site and off-site that are appropriate to be included but are omitted from the topographical survey supplied are included in the schedule, though their positions are shown only indicatively.

The measurement conventions are as follows.

- a) Height, crown spread, and crown clearance are recorded to the nearest half metre (crown spread is rounded up) for dimensions up to 10 m and the nearest whole metre for dimensions over 10 m.
- b) Stem diameter is recorded in millimetres, rounded to the nearest 10 mm (0.01 m).
- c) Estimated dimensions (e.g., for off-site or otherwise inaccessible trees where accurate data cannot be recovered) should be clearly identified as such (e.g., suffixed with a “#”).

Height (m) Tree height measured in metres.

Stem Diameter (mm) Stem diameter in millimetres measured at 1.5m above ground level. Where the stem is divided below 1.5m, measurement is taken as directed by BS 5837 Annex C.

Branch Spread (m) Radial crown spread in metres, measured for each of the four cardinal points of the compass from the centre of the trunk.

Height of Lowest Branch (m)

& Direction of growth Height above ground in metres of the lowest branch and use of the 4 cardinal points of the compass.

Life Stage:

- Y Young** A recently planted or establishing tree that could be transplanted without specialist equipment, i.e., up to 12-14cm stem diameter.
- SM Semi-Mature.** An establishing tree which is still exhibiting apical dominance and has significant growth potential.
- EM Early Mature.** A tree that has reaching its ultimate potential height and has lost its apical dominance, and whose growth rate is slowing down but will still has potential for a significant increase in stem diameter and crown spread and has a significant safe life expectancy remaining.
- M Mature** A tree with limited potential for any increase in size but with reasonable safe useful life expectancy.
- OM Over Mature** A senescent or moribund specimen with a limited safe useful life expectancy.
- V Veteran** A tree of great age for species with important biological, aesthetic, conservation, or cultural value. Trees are in a state of decline due to old age.

Condition of Trees

Physiological Condition (P) An assessment of the physiological condition (i.e., health/vitality) of the tree categorised into:

| | |
|-------------|--|
| Good | A tree in a healthy condition with no significant problems |
| Fair | A tree generally in good health with some problems that can be remediated. |
| Poor | A tree in poor health with significant problems that cannot be remediated. |
| Dead | A tree without enough live material to sustain life. |

Structural Condition (S) An assessment of the structural/safe condition of the tree categorised into:

| | |
|-------------|--|
| Good | A tree in a safe condition with no significant defects. |
| Fair | A tree in a safe condition at present but with defects or with significant defects that can be remediated. |
| Poor | A tree with significant defects that cannot be remediated. |

Notes related to both physiological and structural condition follow the categorization in order support the statement and give greater detail on the true quality and value of the tree.

Preliminary Management Recommendations

These may include further investigations for the presence or extent of decay or climbed inspections, ivy removal or pruning works when access is a non-moveable aspect etc.
(NB this is not intended to be a specification for tree work and further advice maybe

required prior to implementation). Trees assessed as being in apparently immediately hazardous condition will be notified to the client separately as soon as practicable.

Estimated Remaining Life Contribution

This is an estimate of the remaining life contribution in years that the tree or group of trees is expected to have based on species, condition on the site in its current context. The following bands are used:

- <10** Tree is dead or dying and unlikely to contribute beyond 10 years.
- 10+** Tree is assessed as being able to contribute to the site for 10+ years.
- 20+** Tree is assessed as being able to contribute to the site for 20+ years.
- 40+** Tree is assessed as being able to contribute to the site for 40+ years.

Quality and Value Category Grade

| | | |
|----------|--|--------------------|
| U | Trees that cannot be realistically retained | Dark red |
| A | Those trees of HIGH value quality to retain | Light green |
| B | Those trees of MODERATE quality to retain | Mid blue |
| C | Those trees of LOW quality to retain | Grey |

Deadwood Categorisation

Minor Deadwood Less than 50mm in diameter or less than 3m in length

Major Deadwood Greater than 50mm in diameter or greater than 3m in length

Appendix IV Images



Image 1 T36-38 along the site boundary



Image 2 T42-45, along the site boundary



Image 3 T45-60, along site boundary



Image 4 T57-71, along site boundary with G2 in the foreground on the right



Image 5 T72 a hornbeam just inside the current site boundary



Image 6 T73 an ash tree exhibiting signs of ash dieback



Image 7 G3, a cypress hedge along the right side, in the adjacent garden



Image 8 H1 a cypress hedge in the cemetery



Image 9 T76-78 and T80 in the cemetery



Image 10 G1, running along the edge of the northern boundary of the current site,



Image 11 G1, running along the edge of the northern boundary of the current site,



Image 12 G5, running along the southern edge of the site,



Image 13 Scrub and brambles around T17 to T21.



Image 14 Scrub and brambles around T17 to T21.



Image 15 T23 on the adjacent land behind the farm huts.



Image 16 Existing entrance into Woodland Road.

Appendix V Arboricultural Supervision Recording Template

| | | | |
|------------------------------------|------------|-------------------------------|------------|
| Client: | | Planning Ref: | |
| Local Authority: | | Date: | |
| Site Address | | | |
| Proposal: | | | |
| Visit Checklist | Y/N | | Y/N |
| Tree Protection Fencing in place | | Tree protection as approved | |
| Ground Protection in place | | Ground Protection as approved | |
| Tree or Ground protection breached | | Trees damaged | |
| Site Agent briefed by AC | | | |
| AC briefed by Site Agent | | | |
| LPA informed | | | |
| Remedial action required | | | |
| Comments | | | |
| | | | |
| Recommendations | | | |
| | | | |
| Outcome | | | |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommended Work | RPA Annex D (m) |
|------------|--------------------------------|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|--|---------------------------------|-----------------|
| T 1 | White willow <i>Salix alba</i> | 300;160;110 | 3 | 12 | 14 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 5 | 5 | 5 | 5 | P Good, S Fair | Multi stemmed tree with tight unions and included bark in a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | No Action Required at this time | 3.6 |
| T 2 | White willow <i>Salix alba</i> | 450;230;420 | 3 | 12 | 14 | 3 | 3 | 3 | 3 | - | - | SM | 40+ | B2 | 5 | 5 | 5 | 5 | P Good, S Fair | Multi stemmed tree with tight unions and included bark in a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. Forth stem was cut down. | NAR | 7.8 |
| T 3 | Ash <i>Fraxinus excelsior</i> | 210;100 | 2 | 10 | 16 | 3 | 3 | 3 | 3 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Fair | Fused stems. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 2.4 |
| T 4 | White willow <i>Salix alba</i> | 410 | 1 | 9 | 14 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B2 | 4 | 5 | 4 | 2 | P Good, S Fair | Multi stemmed tree with tight unions and included bark in a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 4.8 |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommend Work | RPA Annex D (m) |
|------------|-----------------------------------|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 5 | Ash <i>Fraxinus excelsior</i> | 160 | 1 | 10 | 16 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | No significant defects. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 1.2 |
| T 6 | Oak <i>Quercus robur</i> | 200 | 1 | 9 | 16 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | No significant defects. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 2.1 |
| T 7 | White willow <i>Salix alba</i> | 240, 250 | 2 | 9 | 16 | 3 | 3 | 3 | 3 | - | - | SM | 40+ | B2 | 5 | 5 | 5 | 5 | P Good, S Fair | Multi stemmed tree with tight unions and included bark in a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 4.2 |
| T 8 | Oak <i>Quercus robur</i> | 250 | 1 | 8 | 16 | 3 | 3 | 3 | 3 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Fair | No significant defects. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 2.4 |
| T 9 | Oak <i>Quercus robur</i> | 260 | 1 | 8 | 16 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 2 | 2 | 6 | 2 | P Good, S Fair | Asymmetrical crown, leaning to the south. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 3 |

Appendix VI

Page 52 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommended Work | RPA Annex D (m) |
|------------|---------------------------------------|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|--|---|-----------------|
| T 10 | Oak <i>Quercus robur</i> | 200 | 1 | 16 | 9 | 2 | 2 | 2 | 2 | - | - | SM | <10 | U | 3 | 2 | 4 | 2 | P Poor, S Poor | Tree in poor health with significant deadwood and die back. | Remove and plant a replacement | 2.1 |
| T 11 | Oak <i>Quercus robur</i> | 280 | 1 | 11 | 16 | 4 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 2 | 3 | 5 | 4 | P Good, S Good | Asymmetrical crown. In a field boundary group with an understory hedge of blackthorn, hawthorn and guelder rose. | NAR | 3 |
| T 12 | Oak <i>Quercus robur</i> | 270 | 1 | 10 | 16 | 6 | 6 | 6 | 6 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | Along rear fence | Remove to facilitate the proposed development | 3 |
| T 13 | Oak <i>Quercus robur</i> | 270 | 1 | 9 | 16 | 3 | 3 | 3 | 3 | 3 | W | SM | 40+ | C2 | 4 | 3 | 4 | 4 | P Good, S Poor | Significant damage to the buttress roots. | Remove to facilitate the proposed development | 3 |
| T 14 | Oak <i>Quercus robur</i> | 260 | 1 | 8 | 12 | 2 | 2 | 2 | 2 | 2 | W | SM | 20+ | B2 | 4 | 3 | 4 | 5 | P Good, S Good | Open grown tree on edge of hedge | NAR | 2.7 |
| T 15 | Oak <i>Quercus robur</i> | 170, 220, 160 | 3 | 6 | 10 | 2 | 2 | 2 | 2 | 2 | S | SM | 40+ | C2 | 4 | 3 | 4 | 4 | P Fair S Poor | Open grown tree on edge of hedge. Cavity in stem and root damage and dieback evident. | NAR | 3.9 |
| T 16 | Oak <i>Quercus robur</i> | 120 | 1 | 7 | 16 | 3 | 3 | 3 | 3 | - | - | EM | 20+ | B2 | 3 | 3 | 3 | 3 | P Good, S Good | No significant defects | NAR | 1.5 |
| T 17 | Hawthorn <i>Crataegus monogyna</i> | 80# Ave | 6 | 7 | 7 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | C2 | 3 | 3 | 3 | 3 | P Fair S Fair | Multi stemmed tree with a sparse top | NAR | 2.4 |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommend Work | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|-----|-----|-----|-------------------------|---|---|-----------------|
| T 18 | Hawthorn <i>Crataegus monogyna</i> | 130, 130 | 2 | 6 | 10 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 2 | 3 | 2 | 3 | P Good, S Fair | Twin stem with included bark | NAR | 2.1 |
| T 19 | Birch <i>Betula pendula</i> | 180 | 1 | 10 | 14 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B2 | 3 | 5 | 3 | 1 | P Good, S Fair | Lean Mechanical damage 1-1.5m on west side. | NAR | 2.1 |
| T 20 | Goat willow <i>Salix caprea</i> | 240 | 1 | 6 | 6 | 0 | 0 | 0 | 0 | - | - | SM | 10+ | C2 | 3 | 2 | 3 | 5 | P Good, S Poor | Basal and epicormic growth Lean to the west Pollard with decay in main stem | NAR | 2.4 |
| T 21 | Hawthorn <i>Crataegus monogyna</i> | 250, 120 | 2 | 6 | 10 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | C1 | 3 | 2 | 3 | 3 | P Good, S Fair | Open grown tree with multi stems and included bark | NAR | 3.6 |
| T 22 | Ash <i>Fraxinus excelsior</i> | 180 | 1 | 7 | 16 | 2 | 2 | 2 | 2 | - | - | SM | 40+ | B1 | 3 | 3 | 2 | 3 | P Good, S Good | No significant defects | Remove to facilitate the proposed development | 1.5 |
| T 23 | Oak <i>Quercus robur</i> | 350# | 1 | 8 | 16 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B1 | 4 | 6 | 6 | 6 | P Good, S Good | No significant defects | NAR | 4.2 |
| T 24 | Leyland cypress <i>Cupressus × leylandii</i> | 580 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 4 | 4 | 4 | 4 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 6 |
| T 25 | Leyland cypress <i>Cupressus × leylandii</i> | 440 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2.5 | 2.5 | 2.5 | 2.5 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.8 |
| T 26 | Leyland cypress <i>Cupressus × leylandii</i> | 390 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2.5 | 2.5 | 2.5 | 2.5 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.2 |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommended Work | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|-----|-----|-----|-------------------------|--|------------------|-----------------|
| T 27 | Leyland cypress <i>Cupressus × leylandii</i> | 400 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.2 |
| T 28 | Leyland cypress <i>Cupressus × leylandii</i> | 310 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2 | 2 | 2 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 3 |
| T 29 | Leyland cypress <i>Cupressus × leylandii</i> | 430 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2.5 | 2.5 | 2.5 | 2.5 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.5 |
| T 30 | Leyland cypress <i>Cupressus × leylandii</i> | 340 | 1 | 12 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2 | 2 | 2 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 3.6 |
| T 31 | Leyland cypress <i>Cupressus × leylandii</i> | 350 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2 | 2 | 2 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 3.6 |
| T 32 | Leyland cypress <i>Cupressus × leylandii</i> | 370 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2.5 | 2.5 | 2.5 | 2.5 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.2 |
| T 33 | Leyland cypress <i>Cupressus × leylandii</i> | 410 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2.5 | 2.5 | 2.5 | 2.5 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 4.5 |
| T 34 | Leyland cypress <i>Cupressus × leylandii</i> | 580 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 6 |
| T 35 | Leyland cypress <i>Cupressus × leylandii</i> | 550 | 1 | 14 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 5.1 |

Appendix VI

Page 55 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommendation | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 36 | Leyland cypress <i>Cupressus × leylandii</i> | 370 | 1 | 14 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.2 |
| T 37 | Leyland cypress <i>Cupressus × leylandii</i> | 420 | 1 | 14 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.5 |
| T 38 | Leyland cypress <i>Cupressus × leylandii</i> | 470 | 1 | 13 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 5.1 |
| T 39 | Leyland cypress <i>Cupressus × leylandii</i> | 320 | 1 | 13 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 40 | Leyland cypress <i>Cupressus × leylandii</i> | 260 | 1 | 13 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3 |
| T 41 | Leyland cypress <i>Cupressus × leylandii</i> | 370 | 1 | 13 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.9 |

Appendix VI

Page 56 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommendation | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 42 | Leyland cypress <i>Cupressus × leylandii</i> | 390 | 1 | 13 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.2 |
| T 43 | Ash <i>Fraxinus excelsior</i> | 90 | 1 | 8 | 16 | 1 | 1 | 1 | 1 | - | - | SM | 40+ | C1 | 1 | 1 | 1 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 1.2 |
| T 44 | Leyland cypress <i>Cupressus × leylandii</i> | 180 | 1 | 10 | 20 | 0 | 0 | 2 | 0 | - | - | SM | 40+ | B1 | 2 | 3 | 2 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 1.8 |
| T 45 | Leyland cypress <i>Cupressus × leylandii</i> | 410 | 1 | 11 | 20 | 1 | 1 | 4 | 1 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.2 |
| T 46 | Leyland cypress <i>Cupressus × leylandii</i> | 360 | 1 | 11 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 47 | Hornbeam, <i>Carpinus betulus</i> | 120 | 1 | 10 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B1 | 2 | 2 | 2 | 1 | P Good, S Fair | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 1.8 |

Appendix VI

Page 57 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommend Work | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|--|----------------|-----------------|
| T 48 | Hornbeam, <i>Carpinus betulus</i> | 130 | 1 | 10 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B1 | 2 | 1 | 2 | 2 | P Good, S Fair | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 1.5 |
| T 49 | Ash <i>Fraxinus excelsior</i> | 110 | 1 | 8 | 16 | 1 | 1 | 1 | 1 | - | - | SM | 40+ | C1 | 2 | 3 | 2 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary | NAR | 1.2 |
| T 50 | Leyland cypress <i>Cupressus × leylandii</i> | 250 | 1 | 9 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 2.1 |
| T 51 | Ash <i>Fraxinus excelsior</i> | 100 | 1 | 10 | 13 | 1 | 1 | 1 | 1 | - | - | SM | 40+ | C1 | 3 | 1 | 3 | 1 | P Good, S Fair | No significant defects. Approximately 1.5m beyond boundary | NAR | 1.2 |
| T 52 | Leyland cypress <i>Cupressus × leylandii</i> | 460 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.8 |
| T 53 | Leyland cypress <i>Cupressus × leylandii</i> | 460 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.8 |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommendation | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 54 | Leyland cypress <i>Cupressus × leylandii</i> | 420 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 2 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.5 |
| T 55 | Leyland cypress <i>Cupressus × leylandii</i> | 320 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 56 | Leyland cypress <i>Cupressus × leylandii</i> | 370 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.9 |
| T 57 | Leyland cypress <i>Cupressus × leylandii</i> | 380 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.2 |
| T 58 | Leyland cypress <i>Cupressus × leylandii</i> | 340 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 59 | Leyland cypress <i>Cupressus × leylandii</i> | 320 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |

Appendix VI

Page 59 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommendation | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 60 | Leyland cypress <i>Cupressus × leylandii</i> | 290 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3 |
| T 61 | Leyland cypress <i>Cupressus × leylandii</i> | 300 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.3 |
| T 62 | Leyland cypress <i>Cupressus × leylandii</i> | 290 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.3 |
| T 63 | Leyland cypress <i>Cupressus × leylandii</i> | 330 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 2 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 64 | Leyland cypress <i>Cupressus × leylandii</i> | 330;250 | 2 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | C1 | 2 | 2 | 2 | 2 | P Good, S Fair | Part fail with a swept stem Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.5 |
| T 65 | Leyland cypress <i>Cupressus × leylandii</i> | 270;120 | 1 | 13 | 20 | 0 | 0 | 4 | 0 | - | - | SM | 40+ | C1 | 2 | 2 | 2 | 2 | P Good, S Fair | Part fail with a swept stem Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3 |

Appendix VI

Page 60 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommend Work | RPA Annex D (m) |
|------------|---|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|----------------|-----------------|
| T 66 | Leyland cypress <i>Cupressus × leylandii</i> | 270 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3 |
| T 67 | Leyland cypress <i>Cupressus × leylandii</i> | 340 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.9 |
| T 68 | Leyland cypress <i>Cupressus × leylandii</i> | 340 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 2 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.6 |
| T 69 | Leyland cypress <i>Cupressus × leylandii</i> | 300 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 1 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3.3 |
| T 70 | Leyland cypress <i>Cupressus × leylandii</i> | 270 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 1 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 3 |
| T 71 | Leyland cypress <i>Cupressus × leylandii</i> | 430 | 1 | 13 | 20 | 3 | 3 | 4 | 3 | - | - | SM | 40+ | B1 | 3 | 3 | 3 | 3 | P Good, S Good | No significant defects. Approximately 1.5m beyond boundary Mutual crown suppression | NAR | 4.8 |

Appendix VI

Page 61 of 63

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommended Work | RPA Annex D (m) |
|------------|---|-----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|----|-----|----|-------------------------|---|------------------|-----------------|
| T 72 | Hornbeam, <i>Carpinus betulus</i> | 210;400; 130 | 3 | 14 | 16 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B1 | 3 | 5 | 4 | 3 | P Good, S Fair | Multi stemmed | NAR | 3.6 |
| T 73 | Ash <i>Fraxinus excelsior</i> | 210 | 1 | 13 | 14 | 4 | 4 | 4 | 4 | - | - | SM | 10+ | C1 | 1 | 3 | 5 | 3 | P Poor S Good | Symptoms of ash dieback as it is just starting to flush, small tufty leaflets | NAR | 2.4 |
| T 74 | Oak <i>Quercus robur</i> | 410 | 1 | 16 | 16 | 5 | 5 | 5 | 5 | - | - | EM | 40+ | B1 | 6# | 6# | 6# | 6# | P Good, S Good | 6m back behind site boundary and footpath on railway land. | NAR | 4.8 |
| T 75 | Black locust, <i>Robinia pseudoacacia</i> | 380 | 1 | 10 | 16 | 4 | 4 | 3 | 4 | - | - | SM | 40+ | B1 | 5 | 5 | 5.5 | 5 | P Fair, S Good | Minor crown dieback | NAR | 4.5 |
| T 76 | Hawthorn <i>Crataegus monogyna</i> | 50 | 8 | 8 | 12 | 3 | 3 | 3 | 3 | - | - | SM | 40+ | B1 | 3 | 2 | 2 | 2 | P Good, S Fair | Multi stemmed | NAR | 1.8 |
| T 77 | Hawthorn <i>Crataegus monogyna</i> | 160 | 1 | 10 | 12 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B1 | 3 | 1 | 1 | 4 | P Good, S Fair | Multi stemmed with mutual crown suppression | NAR | 1.8 |
| T 78 | Hawthorn <i>Crataegus monogyna</i> | 190 | 1 | 10 | 12 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B1 | 4 | 4 | 1 | 2 | P Good, S Fair | Multi stemmed with mutual crown suppression | NAR | 2.4 |
| T 79 | Ash <i>Fraxinus excelsior</i> | 120 | 1 | 8 | 16 | 4 | 4 | 4 | 4 | - | - | SM | 40+ | B1 | 3 | 3 | 1 | 3 | P Good, S Good | No significant defects | NAR | 1.5 |
| T 80 | Unknown | 70 | 1 | 6 | 16 | 1 | 1 | 1 | 1 | - | - | SM | 40+ | C1 | 2 | 2 | 1 | 1 | P Good, S Good | No significant defects | NAR | 0.9 |

APPENDIX VI - TREE SURVEY RECORDS

Date of Survey - 1st November 2021

| Tree Id No | Tree Species | Stem Diam (mm) | Stem No | Tree Hgt (m) | Ult Hgt (m) | Crown Height N, E, S, W (m) | | | | FSB Hgt (m) | FSB Dir | Life Stage | Life Exp | BS 5837 Cat | Canopy Spread N, E, S, W (m) | | | | Phys & Struct Condition | Comments | Recommend Work | RPA Annex D (m) |
|------------|--|----------------|---------|--------------|-------------|-----------------------------|---|---|---|-------------|---------|------------|----------|-------------|------------------------------|---|---|---|-------------------------|---|---|-----------------|
| G 1 | Mixed species | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | Mostly hawthorn and bramble that has self set. No significant defects | NAR | N/A |
| G 2 | Mixed species | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | Mostly hawthorn and bramble that has self set. No significant defects | NAR | N/A |
| G 3 | Leyland cypress <i>Cupressus</i> × <i>leylandii</i> | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B2 | 2 | 2 | 2 | 2 | P Good, S Good | Row of cypress trees in an adjacent garden, planted as a hedge. No significant defects | NAR | N/A |
| G 4 | Mixed species | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B1 | 4 | 4 | 4 | 4 | P Good, S Good | Mostly hawthorn and bramble that has self set. No significant defects | NAR | N/A |
| G 5 | Mixed species | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B2 | 4 | 4 | 4 | 4 | P Good, S Good | Mostly hawthorn, birch, and bramble that has self set. No significant defects | Remove to facilitate the proposed development | N/A |
| H 1 | Leyland cypress <i>Cupressus</i> × <i>leylandii</i> | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B2 | 2 | 2 | 2 | 2 | P Good, S Good | Row of cypress trees in an adjacent garden, planted as a hedge. No significant defects | NAR | N/A |
| H 2 | Leyland cypress <i>Cupressus</i> × <i>leylandii</i> | Vary | Many | 6 | 16 | 0 | 0 | 0 | 0 | - | - | SM | 40+ | B3 | 2 | 2 | 2 | 2 | P Good, S Good | Row of cypress trees in an adjacent garden, planted as a hedge. No significant defects | NAR | N/A |